



①	FINISHED GRADE
②	BUBBLER
③	PVC NIPPLE, SCHEDULE 40
④	INSTALL NDS-FLO MANAGEMENT ADJUSTABLE INLINE SPRING CHECK VALVE CV-0500-FM (GRAY PVC) BELOW BUBBLERS TO STOP DRAINAGE WHERE LOW HEAD DRAINAGE MAY OCCUR. (TYPICAL)
⑤	1/2" SCHEDULE 80 PVC MALE ADAPTER (GRAY). MALE ADAPTER MUST BE GRAY IN COLOR. WHITE PVC SHALL NOT BE INSTALLED AT THIS LOCATION.
⑥	1/2" IPS FLEXIBLE PVC HOSE (.840 O.D.) USE ONLY IPS WELD ON #795 SOLVENT CEMENT ON THIS HOSE.
⑦	1/2" SCHEDULE 80 PVC MALE ADAPTER
⑧	SxSxT SCHEDULE 80 PVC TEE OR SxT ELL IN PVC LATERAL LINE

## THE CITY OF WEST SACRAMENTO - STANDARD DETAIL



APPROVED: Aug. X, 2025

STANDARD  
DETAIL #

**713**

TITLE:

**SHRUB BUBBLER WITH  
FLEXIBLE RISER**

